
HIGHBANKS SOLAR, LLC

12.5 MW AC (18.9 MW DC)
TOWN OF LEICESTER, LIVINGSTON COUNTY, NY

SHEET INDEX			
SHEET#	SHEET TITLE	DATED	REVISION DATE
	COVER	6/19/2024	
C1.0	EXISTING CONDITIONS	6/19/2024	
C2.0	OVERALL IMPROVEMENT PLAN	6/19/2024	
C2.1	SITE PLAN	6/19/2024	
C2.2	SITE PLAN	6/19/2024	
C2.3	SITE PLAN	6/19/2024	
C2.4	SITE PLAN	6/19/2024	
C2.5	SITE PLAN	6/19/2024	
C3.0	OVERALL GRADING AND UTILITY PLAN	6/19/2024	
C3.1	GRADING AND UTILITY PLAN	6/19/2024	
C3.2	GRADING AND UTILITY PLAN	6/19/2024	
C3.3	GRADING AND UTILITY PLAN	6/19/2024	
C3.4	GRADING AND UTILITY PLAN	6/19/2024	
C3.5	GRADING AND UTILITY PLAN	6/19/2024	
C4.0	OVERALL EROSION AND SEDIMENT CONTROL PLAN	6/19/2024	
C4.1	EROSION AND SEDIMENT CONTROL PLAN	6/19/2024	
C4.2	EROSION AND SEDIMENT CONTROL PLAN	6/19/2024	
C4.3	EROSION AND SEDIMENT CONTROL PLAN	6/19/2024	
C4.4	EROSION AND SEDIMENT CONTROL PLAN	6/19/2024	
C4.5	EROSION AND SEDIMENT CONTROL PLAN	6/19/2024	
C4.6	EROSION AND SEDIMENT CONTROL PLAN	6/19/2024	
C5.0	SITE VEGETATION AND HABITAT PLAN	6/19/2024	
C6.0	SITE DETAILS	6/19/2024	
C6.1	SITE DETAILS	6/19/2024	
C7.0	DECOMMISSIONING PLAN	6/19/2024	
C7.1	DECOMMISSIONING PLAN	6/19/2024	

THE TOTAL STATE OF THE PARTY OF
ATGREAM'S ROKE
OLD HIGHBANKS ROAD
CONTRACTOR OF THE PROPERTY OF



-CLOSEST KNOWN HYDRAN

TOWN ENGINEER DATE

PLANNING BOARD CHAIRMAN DATE

THIS IS TO CERTIFY THAT TO THE BEST OF OUR KNOWLEDGE, INFORMATION AND BELIEF - THESE PLANS AND SPECIFICATIONS ARE IN ACCORDANCE WITH APPLICABLE REQUIREMENTS OF THE BUILDING CODE, FIRE CODE, AND ENERGY CONSERVATION CONSTRUCTION CODE OF NEW YORK STATE.

APPLICANT INFORMATION:

HIGHBANKS SOLAR, LLC ATTN: STEVE ONDISHIN 110 EDISON PLACE SUITE 312 NEWARK, NJ 07102


PROJECT LOCATION


2449 HIGHBANKS ROAD TOWN OF LEICESTER LIVINGSTON COUNTY NEW YORK TAX ID: 105-1-8.11 JUNE 19, 2024 HUNT NO. 3576.001





4 Commercial Street, Suite 300, Rochester, NY 14614 P: 585-327-7950 F: 585-327-7949


Offices: Horseheads | Rochester | Towanda | Binghamton | Albany





















































- THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION CONTROL AND MAINTENANCE OF SOIL EROSION AND SEDIMENT CONTROL FACILITIES TO INSURE PROPER FUNCTIONING OF SAID FACILITIES (DURING CONSTRUCTION).
- AFTER THE PROJECT HAS BEEN COMPLETED, THE CONTRACTOR SHALL HAVE THE RESPONSIBILITY FOR INSURING THAT ALL TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES HAVE BEEN REMOVED OR REPLACED BY PERMANENT CONTROLS.
- ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED FOR MORE THAN 5 DAYS, AND NOT SUBJECT TO CONSTRUCTION TRAFFIC, WILL IMMEDIATELY RECEIVE A TEMPORARY SEEDING. IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER. THE DISTURBED AREAS WILL BE MULCHED WITH STRAW OR EQUIVALENT MATERIAL, AT A RATE OF 2.0 TONS PER ACRE, ACCORDING TO STATE STANDARDS.
- PERMANENT VEGETATION TO BE SEEDED OR SODDED ON ALL EXPOSED AREAS WITHIN FIVE (5) DAYS AFTER FINAL GRADING. MULCH AS NECESSARY FOR SEED PROTECTION AND ESTABLISHMENT.

II. EROSION & SEDIMENT POLLUTION CONTROL (E & SPC) GUIDELINES

- EROSION AND SEDIMENT POLLUTION CONTROL FACILITIES AND PRACTICES, UTILIZED IN THE CONSTRUCTION OF THE PROJECT, SHALL BE CONSISTENT WITH THE LATEST EDITIONS OF THE NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL, THE NEW YORK STATE STORMWATER MANAGEMENT DESIGN MANUAL, AND THE NEW YORK STATE SPDES GENERAL PERMIT FOR STORMWATER DISCHARGES.
- NATURAL VEGETATION SHALL BE RETAINED, PROTECTED, AND SUPPLEMENTED, AS FEASIBLE PRIOR TO AND DURING CONSTRUCTION.
- 3. CUT AND FILL SLOPES SHALL BE BROUGHT TO FINAL PROPOSED GRADES AS SOON AS POSSIBLE IN THE CONSTRUCTION SEQUENCES. AND SEEDED AND MULCHED.
- EROSION AND SEDIMENT POLLUTION CONTROL FACILITIES (CHECK DAMS, FILTER FABRIC FENCING, STABILIZED CONSTRUCTION ENTRANCES, SEDIMENT TRAPS, AND OTHER ACCEPTABLE IMPLEMENTED FACILITIES) SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION UNTIL COMPLETE SITE STABILIZATION.
- HEAVY CONSTRUCTION EQUIPMENT SHALL BE KEPT AS CLOSE TO THE WORK AREA AS PRACTICED TO MINIMIZE DISTURBANCE OF SOIL ALREADY STABILIZED OR UNDISTURBED.
- 6. TOPSOIL AND OTHER SOIL REMOVED DURING CONSTRUCTION SHALL BE STOCKPILED IN A SUITABLE LOCATION CLEAR FROM ANY STORMWATER DRAINAGE COURSES. STOCKPILES SHALL BE STABILIZED TO PREVENT EROSION.
- VEGETATIVE STABILIZATION SHALL BE PERIODICALLY INSPECTED FOR SUFFICIENT GROWTH AND PROGRESS. AREAS NOT RESPONDING SHALL BE PROMPTLY RESEEDED AND REMULCHED AS SOON AS POSSIBLE. AREAS SHOWING SIGNS OF EROSION PRIOR TO STABILIZATION SHALL BE GRADED, RESEEDED, AND REMULCHED AS SOON AS POSSIBLE. SOD OR EROSION CONTROL FABRIC SHALL BE UTILIZED WHERE ADEQUATE STABILIZATION IS NOT
- ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED BEFORE BEGINNING EARTH MOVING ACTIVITIES, OR IN THEIR PROPER SEQUENCE, AND MAINTAINED UNTIL PERMANENT PROTECTION IS ESTABLISHED.
- 9. A STABILIZED CONSTRUCTION ENTRANCE PAD CLEAN STONE WILL BE PLACED AT ALL CONSTRUCTION DRIVEWAYS IMMEDIATELY AFTER INITIAL SITE DISTURBANCE AS PER THE DETAIL ON THIS SHEET.
- 10. ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED FOR MORE THAN 5 DAYS, AND NOT SUBJECT TO CONSTRUCTION TRAFFIC, WILL RECEIVE A TEMPORARY SEEDING. IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER. THE DISTURBED AREAS WILL BE MULCHED WITH STRAW OR EQUIVALENT MATERIAL, AT A RATE OF 2.0 TONS PER ACRE, ACCORDING TO STATE STANDARDS.
- 11. PERMANENT VEGETATION TO BE SEEDED ON ALL EXPOSED AREAS WITHIN FIVE (5) DAYS AFTER FINAL GRADING. MULCH TO BE USED AS NECESSARY FOR PROTECTION UNTIL SEEDING IS ESTABLISHED.
- 12. THE APPLICATION OF TOPSOIL, SEEDING, AND MULCHING FOR DISTURBED AREAS SHALL BE CONSISTENT WITH THE STANDARD GENERAL PRACTICES FOR CONSTRUCTION.
- 13. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN EROSION AND SEDIMENT CONTROL MEASURES UNTIL ALL AREAS HAVE BEEN PERMANENTLY STABILIZED.
- 14. ANY SEDIMENT TRACKED ONTO PUBLIC RIGHT00F-WAYS SHALL BE SWEPT AT THE END OF EACH WORKING DAY.
- 15. ALL DEBRIS GENERATED DURING SITE PREPARATION ACTIVITIES SHALL BE LEGALLY DISPOSED OF OFF SITE.
- 16. ADDITIONAL EROSION CONTROL MEASURES SHALL BE IMPLEMENTED AS CONDITIONS WARRANT OR AS DIRECTED BY THE OWNER OR OWNER'S REPRESENTATIVE.
- 17. SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSPECTED AND MAINTAINED ON A DAILY BASIS DURING CONSTRUCTION TO ENSURE THEIR CONTINUED FUNCTIONALITY.
- 18. DUST SHALL BE CONTROLLED BY SPRINKLING OR OTHER APPROVED METHODS AS NECESSARY, OR AS DIRECTED BY THE OWNER OR OWNER'S REPRESENTATIVE.

III. MAINTENANCE AND REPAIR OF EROSION AND SEDIMENT POLLUTION CONTROL FACILITIES

- PROPER MAINTENANCE AND REPAIR OF EROSION AND SEDIMENT CONTROL FACILITIES ARE NECESSARY TO THE EFFECTIVENESS OF THE EROSION AND SEDIMENT POLLUTION CONTROL FACILITIES.
- DISTURBED GROUND SURFACES SHALL BE SPRINKLED WITH WATER, AS NEEDED, TO LIMIT THE FORMATION AND MIGRATION OF AIRBORNE DUST.
- OPERATIONAL MEASURES SHALL BE EMPLOYED DURING CONSTRUCTION TO PREVENT THE SPILLS OF FUELS AND LUBRICANTS. IF A SPILL OCCURS, IT SHALL BE CONTROLLED IMMEDIATELY TO PREVENT ITS ENTRY INTO OFF-SITE AREAS INCLUDING ADJACENT STORM SEWER.
- ANY TEMPORARY EROSION CONTROL FACILITY SHALL REMAIN FUNCTIONAL UNTIL VEGETATIVE COVER IS SUFFICIENTLY ESTABLISHED WITHIN THE RESPECTIVE TRIBUTARY DRAINAGE AREA.
- ANY DEBRIS ACCUMULATED IN EROSION AND SEDIMENT CONTROL FACILITIES SHALL BE REMOVED AND PROPERLY DISPOSED. THESE FACILITIES SHALL BE CHECKED DAILY AND AFTER RAINFALL EVENTS, AND REALIGNED AS NEEDED. SEDIMENT SHALL BE REMOVED WHEN IT REACHES THE FOLLOWING DEPTHS:

SILT FENCE - 1/2 HEIGHT

ROCK OUTLET TRAP - 1/2 TRAP DEPTH (DEPTH VARIES)

INLET PROTECTION - 1 INCH

NOTE: DISTURBED AREAS SHALL BE CONSIDERED AS PERMANENTLY STABILIZED WHEN A MINIMUM COVER OF 80% HAS BEEN ESTABLISHED.

IV. MULCHING AND SEEDING REQUIREMENTS

TEMPORARY SEED REQUIREMENTS

SEEDING:

a. APPLY LAWN MIX

*SPRING OR SUMMER OR EARLY FALL, THEN SEED THE AREA WITH RYEGRASS (ANNUAL OR PERENNIAL) AT 30 LBS. PER ACRE

*LATE FALL OR EARLY WINTER, THEN SEED CERTIFIED 'AROOSTOOK' WINTER RYE (CEREAL RYE) AT 100 LBS. PER ACRE) b. APPLY SEED WITH MECHANICAL SEEDER. OPTIMUM SEEDING DEPTH IS ONE INCH

(EXCEPT SANDY SOILS, 2 INCHES) c. WHERE FEASIBLE, EXCEPT WHERE EITHER A CULTIPAKER TYPE SEEDER OR HYDRO-SEEDER IS USED. THE SEEDBED SHALL BE FIRMED FOLLOWING SEEDING OPERATIONS WITH A ROLLER, OR LIGHT DRAG. SEEDING OPERATIONS SHOULD BE ON THE CONTOUR.

MULCHING

- a. MULCH MATERIALS SHALL BE UN-ROTTED HAY OR STRAW AT A RATE OF 2.0 TO 3.0 TONS PER ACRE, OR 70 TO 90 POUNDS PER 1,000 SQUARE FEET. MULCH SHOULD NOT BE GROUND OR CHOPPED INTO SHORT PIECES.
- b. SPREAD UNIFORMLY BY HAND OR MECHANICALLY SO THAT APPROXIMATELY 75 PERCENT TO 95 PERCENT OF THE SOIL SURFACE WILL BE COVERED.
- c. MULCH ANCHORING SHALL BE ACCOMPLISHED IMMEDIATELY AFTER PLACEMENT TO MINIMIZE LOSS BY WIND OR WATER. ACCEPTABLE ANCHORING TO INCLUDE WOOD FIBER HYDROMULCH OR OTHER SPRAYABLE PRODUCTS APPROVED FOR EROSION CONTROL (NYLON WEB OR MESH) MAY BE USED IF APPLIED ACCORDING TO MANUFACTURERS' SPECIFICATION.

PERMANENT SEED REQUIREMENTS

SEEDBED PREPARATION

a. REMOVE ALL ROCKS AND DEBRIS FROM SOIL SURFACE. b. INSPECT SEEDBED JUST BEFORE SEEDING. IF TRAFFIC HAS LEFT THE SOIL COMPACT, THE AREA MUST BE RE-TILLED AS ABOVE.

- a. PERMANENT SEEDING SHALL BE AS SHOWN ON SHEET C5.0
- b. APPLY SEED WITH MECHANICAL SEEDER OR BY HYDROSEEDING. OPTIMUM SEEDING DEPTH IS ONE INCH (EXCEPT SANDY SOILS, 2 INCHES).
- c. WHERE FEASIBLE, EXCEPT WHERE EITHER A CULTIPAKER TYPE SEEDER OR HYDRO-SEEDER IS USED, THE SEEDBED SHALL BE FIRMED FOLLOWING SEEDING OPERATIONS WITH A ROLLER, OR LIGHT DRAG. SEEDING OPERATIONS SHOULD BE ON THE CONTOUR.

MULCHING

- a. MULCH MATERIALS SHALL BE UN-ROTTED STRAW AT A RATE OF 2.0 TO 3.0 TONS PER ACRE, OR 70 TO 90 POUNDS PER 1,000 SQUARE FEET. MULCH SHOULD NOT BE GROUND OR CHOPPED INTO SHORT PIECES.
- b. SPREAD UNIFORMLY BY HAND OR MECHANICALLY SO THAT APPROXIMATELY 75 PERCENT TO 95 PERCENT OF THE SOIL SURFACE WILL BE COVERED.
- c. MULCH ANCHORING SHALL BE ACCOMPLISHED IMMEDIATELY AFTER PLACEMENT TO MINIMIZE LOSS BY WIND OR WATER. ACCEPTABLE ANCHORING TO INCLUDE WOOD FIBER HYDROMULCH OR OTHER SPRAYABLE PRODUCTS APPROVED FOR EROSION CONTROL (NYLON WEB OR MESH) MAY BE USED IF APPLIED ACCORDING TO MANUFACTURERS' SPECIFICATION.

V. LANDSCAPE PLANTING REQUIREMENTS

- ALL PLANT MATERIAL SHALL CONFORM TO THE MINIMUM GUIDELINES ESTABLISHED BY THE AMERICAN STANDARD FOR NURSERY STOCK PUBLISHED BY THE AMERICAN NURSERY AND LANDSCAPE ASSOCIATION.
- ANY PROPOSED SUBSTITUTIONS OF PLANT MATERIAL SHALL BE MADE WITH MATERIAL EQUIVALENT TO THE DESIRED MATERIAL IN OVERALL FORM, HEIGHT, BRANCHING HABIT, FLOWER, LEAF, COLOR, FRUIT AND CULTURE. PROPOSED SUBSTITUTIONS WILL ONLY BE CONSIDERED IF SUBMITTED WITH ENUMERATED REASONS WHY SUBSTITUTIONS ARE PROPOSED.
- CAUTION SHALL BE USED NOT TO EXTEND MULCH LAYER ABOVE SOIL LEVEL AT 'RUNKS/STEMS OF INSTALLED PLANT MATERIAL.
- ALL PLANT MATERIALS SHALL BE GUARANTEED FOR ONE YEAR FOLLOWING DATE OF
- 5. THE LANDSCAPE CONTRACTOR SHALL CLEAN UP AND REMOVE ANY DEBRIS FROM THE SITE CAUSED BY THE LANDSCAPE CONTRACTOR.


VI. CONSTRUCTION SEQUENCING

- 1. INSTALL STABILIZED CONSTRUCTION ENTRANCE AND PERIMETER PROTECTION
- ROUGH GRADE SITE ENTRANCE AND ACCESS ROADWAY AS SHOWN IN PLANS.
- INSTALL TEMPORARY LAYDOWN AREAS AND GRAVEL ACCESS ROADS.
- TEMPORARILY STABILIZE ALL DISTURBED AREAS.
- INSTALL UTILITIES, RACKING, MODULES AND ALL OTHER SITE IMPROVEMENTS. PROVIDE PERMANENT VEGETATION ON ALL DISTURBED AREAS.
- REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROLS ONCE 80% STABILIZATION HAS BEEN ACHIEVED.

VII. NYSDEC SPDES GENERAL PERMIT (GP-0-20-001) COMPLIANCE


PER NYSDEC SPDES GENERAL PERMIT 0-15-002, AT NO POINT DURING CONSTRUCTION SHALL GREATER THAN 5 ACRES OF THE PROJECT SITE BE DISTURBED AT ONE TIME WITHOUT PRIOR WRITTEN AUTHORIZATION FROM THE DEPARTMENT. COMPLIANCE WITH THE CONDITIONS BELOW IS REQUIRED FOR PROJECTS WHICH EXCEED 5-ACRES OF DISTURBANCE AT ANY GIVEN TIME:

- A. THE OWNER OR OPERATOR SHALL HAVE A QUALIFIED INSPECTOR CONDUCT AT LEAST TWO (2) SITE INSPECTIONS IN ACCORDANCE WITH PART IV.C. OF THIS PERMIT EVERY SEVEN (7) CALENDAR DAYS, FOR AS LONG AS GREATER THAN FIVE (5) ACRES OF SOIL REMAIN DISTURBED. THE TWO (2) INSPECTIONS SHALL BE SEPARATED BY A MINIMUM OF TWO (2) FULL CALENDAR DAYS.
- B. IN AREAS WHERE SOIL DISTURBANCE ACTIVITY HAS TEMPORARILY OR PERMANENTLY CEASED, THE APPLICATION OF SOIL STABILIZATION MEASURES MUST BE INITIATED BY THE END OF THE NEXT BUSINESS DAY AND COMPLETED WITHIN SEVEN (7) DAYS FROM THE DATE THE CURRENT SOIL DISTURBANCE ACTIVITY CEASED. THE SOIL STABILIZATION MEASURES SELECTED SHALL BE IN CONFORMANCE WITH THE TECHNICAL STANDARD, NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL, DATED NOVEMBER 2016.
- C. THE OWNER OR OPERATOR SHALL PREPARE A PHASING PLAN THAT DEFINES MAXIMUM DISTURBED AREA PER PHASE AND SHOWS REQUIRED CUTS AND FILLS.
- D. THE OWNER OR OPERATOR SHALL INSTALL ANY ADDITIONAL SITE-SPECIFIC PRACTICES NEEDED TO PROTECT WATER QUALITY.
- E. THE OWNER OR OPERATOR SHALL INCLUDE THE REQUIREMENTS ABOVE IN THEIR



- ALL TOOLS AND EQUIPMENT UTILIZED DURING ANY CONCRETE CONSTRUCTION, INCLUDING HAND TOOLS, WHEELBARROWS, TRUCKS, CHUTES SHALL UTILIZE THE CONCRETE WASHOUT AREA.
- WASHOUT AREA TO BE MAINTAINED AND CLEANED OUT AT 75% CAPACITY TO PREVENT WASHWATER AND/OR SOLIDS FROM EXITING THE WASHOUT TRAP.

CONCRETE WASH OUT DETAIL



50' MIN. **PAVEMENT** 6" MIN. THE TOTAL PROPERTY OF THE TERMS CLOTH **PROFILE EXISTING GROUND** -50' MIN. EXISTING — **PAVEMENT** MIN. PLAN VIEW

CONSTRUCTION NOTES FOR STABILIZED CONSTRUCTION ENTRANCE

- STONE SIZE USE 2" STONE, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT.
- LENGTH AS REQUIRED, BUT NOT LESS THAN 50 FEET.

SCALE: NOT TO SCALE

- THICKNESS NOT LESS THAN 6 INCHES. WIDTH - 24 FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS
- OR EGRESS OCCURS. FILTER CLOTH - WILL BE PLACED OVER ENTIRE AREA PRIOR TO PLACING OF STONE. FILTER
- CLOTH WILL NOT BE REQUIRED ON A SINGLE RESIDENCE LOT SURFACE WATER - ALL SURFACE WATER FLOWING OR DIRECTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A
- MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT FRACKING OR FLOWING IF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANEST OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAT MUST BE REMOVED
- IMMEDIATELY WASHING - WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY. WHEN WASHING IS REQUIRED. IT SHALL BE DONE ON AN AREA
- STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

STABILIZED CONSTRUCTION ENTRANCE

SOIL STOCKPILE DETAIL

AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE.

MAXIMUM SLOPE OF STOCKPILE SHALL BE 1:2.

SEE SILT SOCK INSTALLATION DETAIL THIS SHEET.

THEN STABILIZED WITH SEED & MULCH.

MAX. 2% SLOPE

SOIL STOCKPILING NOTES:

INSTALLATION:

NOTES:

UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE SURROUNDED WITH SILT SOCK AND

STABILIZE ENTIRE PILE WITH SEED &

MULCH OR PLASTIC COVER

8" SILT SOCK

WHEN INSTALLING RUNNING LENGTHS OF COMPOST SOCKS, BUTT THE SECOND SOCK TIGHTLY AGAINST THE FIRST. DO NOT OVERLAP THE ENDS. STAKE THE SOCKS AT EACH END AND 10' ON CENTER.

MAX. 2% SLOPE

STAKES SHOULD BE DRIVEN THROUGH THE MIDDLE OF THE SOCK. LEAVING 2 - 3 INCHES OF THE STAKE PROTRUDING ABOVE THE SOCK AND AT LEAST 12" IN THE GROUND. WHEN COMPOST SOCKS ARE USED FOR FLAT GROUND APPLICATIONS, DRIVE THE STAKES STRAIGHT DOWN; WHEN INSTALLING WATTLES ON SLOPES, DRIVE THE STAKES PERPENDICULAR TO THE SLOPE.

DRIVE THE FIRST END STAKE OF THE SECOND SOCK AT AN ANGLE TOWARD THE FIRST SOCK IN ORDER TO HELP ABUT THEM TIGHTLY TOGETHER.

INSTALLATION NOTES

- COMPOST SOCKS SHALL BE INSTALLED PRIOR TO ANY LAND-DISTURBING ACTIVITIES.
- COMPOST SOCKS SHALL BE "SILT SOCK", "FILTEREXX" OR OTHER APPROVED FILTER FABRIC SOCK COMPOST SOCKS SHALL BE FILLED WITH WOOD CHIPS OR COMPOST. SEE SPECIFICATIONS FOR APPROVED COMPOSITION OF WOOD CHIPS OR COMPOST
 - NOT FOR USE IN CONCENTRATED FLOW AREAS.
- COMPOST SOCKS SHALL BE INSTALLED PER MANUFACTURERS SPECIFICATIONS.
- ON SLOPES, COMPOST SOCKS SHOULD BE INSTALLED ON CONTOUR WITH A SLIGHT DOWNWARD ANGLE AT THE END OF THE ROW IN ORDER TO PREVENT PONDING AT THE MID SECTION.
- RUNNING LENGTHS OF SOCKS SHOULD BE ABUTTED FIRMLY TO ENSURE NO LEAKAGE AT THE ABUTMENTS. COMPOST SOCK SHALL BE IN CONSTANT CONTACT WITH THE GROUND SURFACE.
- 9. WOOD STAKES SHALL BE USED TO SECURE THE WATTLES. 1/2" TO 5/8" REBAR IS ALSO ACCEPTABLE. BE SURE TO USE A STAKE THAT IS LONG ENOUGH TO PROTRUDE SEVERAL INCHES ABOVE THE WATTLE.

COMPOST OR SILT SOCK INSTALLATION DETAIL SCALE: NOT TO SCALE

— ADJACENT ROLLS TIGHTLY ABUT 2"x 2" WOOD STAKES

COMPOST SOCKS - DETAIL A

SEDIMENT ACCUMULATED BEHIND WATTLE SHALL BE REMOVED WHEN SEDIMENT HAS ACCUMULATED TO ONE-HALF THE DIAMETER OF THE WATTLE.

PROJECT NO: 3576-001

ONTROL

ERS

DRAWN BY:

CHECKED BY:

JUNE 19, 2024


PME 0

AR S

Z E

 \circ

Ш S AN 0 S $\mathbf{\Omega}$ \mathbf{B} 工 0 H G HG Δ Ш



NO NOT CUT LEADER *STAKE TREES UP TO 12' HIGH WITH TWO 2 ½ SQ. HARDWOOD STAKES PER TREE GUY TREES OVER 20 FT. WITH THREE DEADMEN OF GROUND ANCHORS PER TREE * FOR B&B TREES. REMOVE TOP 1/3 OF BALL WRAP CUT METAL BASKET IN AT LEAST FOUR LOCATIONS CIRCLING ROOT BALL RUBBER HOSE HALFWAY UP TREE 2 STANDS GALV. WIRE, TWISTED TILL TIGHT HARDWOOD STAKES MIN 8 FT. LONG SET 1/8 OF ROOT BALL ABOVE FINISH GRADE 3-5" HIGH SAUCER 4-6" MULCH UNDISTURBED SUBBASE 2 TIMES DIA. OF ROOT BALL

MODULE RACK 1X PORTRAIT @ +/- 52° TILT

DRAWN BY:

CHECKED BY:

JUNE 19, 2024

NOTE: DETAIL SHOWN FOR SCHEMATIC PURPOSES. FINAL DETAILS ARE INCLUDED IN THE STRUCTURAL PLANS.

PANEL RACK DETAIL

SCALE: N.T.S.

SCALE: N.T.S.

GEOGRID MATERIAL NOTES: GENERAL NOTES:

(I.E. PROVIDE ACCESS FOR MOWING, EQUIPMENT REPAIR OR MAINTENANCE, ETC.). 2. LIMITED USE PERVIOUS ACCESS ROAD IS LIMITED TO LOW IMPACT IRREGULAR MAINTENANCE ACCESS ASSOCIATED WITH RENEWABLE ENERGY PROJECTS IN NEW YORK STATE.

USE OF THIS DETAIL/CRITERION IS LIMITED TO ACCESS ROADS USED ON AN OCCASIONAL BASIS ONLY


- REMOVE STUMPS, ROCKS AND DEBRIS AS NECESSARY. FILL VOIDS TO MATCH EXISTING NATIVE SOILS AND COMPACTION LEVEL
- 4. REMOVED TOPSOIL MAY BE SPREAD IN ADJACENT AREAS AS DIRECTED BY THE PROJECT ENGINEER. COMPACT TO THE DEGREE OF THE NATIVE INSITU SOIL. DO NOT PLACE IN AN AREA THAT IMPEDES STORMWATER DRAINAGE.
- GRADE ROADWAY, WHERE NECESSARY, TO NATIVE SOIL AND DESIRED ELEVATION. MINOR CRADING FOR CROSS SLOPE CUT AND FILL MAY BE REQUIRED.
- 6. REMOVE REFUSE SOILS AS DIRECTED BY THE PROJECT ENGINEER. DO NOT PLACE IN AN AREA THAT IMPEDES STORMWATER DRAINAGE.
- ROADWAY WIDTH TO BE DETERMINED BY CLIENT.
- THE LIMITED USE PERVIOUS ACCESS ROAD CROSS SLOPE SHALL BE 2% IN MOST CASES AND SHOULD NOT EXCEED 6%. THE LONGITUDINAL SLOPE OF THE ACCESS DRIVE SHOULD NOT EXCEED 15%.
- 9. LIMITED USE PERVIOUS ACCESS ROAD IS NOT INTENDED TO BE UTILIZED FOR CONSTRUCTION WHICH MAY SUBJECT THE ACCESS TO SEDIMENT TRACKING. THIS SPECIFICATION IS TO BE DEVELOPED FOR POST-CONSTRUCTION USE. SOIL RESTORATION PRACTICES MAY BE APPLICABLE TO RESTORE CONSTRUCTION RELATED COMPACTION TO PRE-EXISTING CONDITIONS AND SHOULD BE VERIFIED BY SOIL PENETROMETER READINGS. THE PENETROMETER READINGS SHALL BE COMPARED TO THE RESPECTIVE RECORDED READINGS TAKEN PRIOR TO CONSTRUCTION, EVERY 100 LINEAR FEET ALONG THE PROPOSED ROADWAY.
- 10. TO ENSURE THAT SOIL IS NOT TRACKED ONTO THE LIMITED USE PERVIOUS ACCESS ROAD, IT SHALL NOT BE USED BY CONSTRUCTION VEHICLES TRANSPORTING SOIL, FILL MATERIAL, ETC. IF THE LIMITED USE PERVIOUS ACCESS IS COMPLETED DURING THE INITIAL PHASES OF CONSTRUCTION, A STANDARD NEW YORK STATE STABILIZED CONSTRUCTION ACCESS SHALL BE CONSTRUCTED AND UTILIZED TO REMOVE SEDIMENT FROM CONSTRUCTION VEHICLES AND EQUIPMENT PRIOR TO ENTERING THE LIMITED USE PERVIOUS ACCESS ROAD FROM ANY LOCATION ON, OR OFF SITE. MAINTENANCE OF THE PERVIOUS ACCESS ROAD WILL BE REQUIRED IF SEDIMENT IS OBSERVED WITHIN THE CLEAN STONE.
- 11. THE LIMITED USE PERVIOUS ACCESS ROAD SHALL NOT BE CONSTRUCTED OR USED UNTIL ALL AREAS SUBJECT TO RUNOFF ONTO THE PERVIOUS ACCESS HAVE ACHIEVED FINAL STABILIZATION.
- 12. THE LIMITED USE PERVIOUS ACCESS ROAD SHALL HAVE A WELL-ESTABLISHED PERENNIAL VEGETATIVE COVER, WHICH SHALL CONSIST OF A UNIFORM VEGETATION (I.E. BUFFER), 20 FEET WIDE AND PARALLEL TO THE DOWN GRADIENT SIDE OF THE ACCESS ROAD. POST-CONSTRUCTION OPERATION AND MAINTENANCE PRACTICES WILL MAINTAIN THIS VEGETATIVE COVER TO ENSURE FINAL STABILIZATION FOR THE LIFE OF THE ACCESS ROAD.
- 13. CRUSHED STONE CAP TO BE INSTALLED ON ANY PORTION OF THE PERMANENT PERVIOUS ACCESS ROAD THAT WILL BE INSTALLED AND USED DURING CONSTRUCTION. WOVEN GEOTEXTILE (MIRAFI 500X OR EQUAL) SHALL BE PLACED BETWEEN CRUSHED STONE AND CLEAN STONE. UPON FINAL STABILIZATION, THE CAP SHALL BE REMOVED AND THE PERVIOUS STONE SECTION SHALL HAVE ADDITIONAL STONE ADDED AND GRADED AS NEEDED.


- THE GEOGRID, OR COMPARABLE PRODUCT, IS INTENDED FOR USE FOR ALL CONDITIONS, IN ORDER TO ASSIST IN MATERIAL SEPARATION FROM NATIVE SOILS AND PRESERVE ACCESS LOADS. GRAVEL FILL MATERIAL SHALL CONSIST OF 1-4" CLEAN, DURABLE, SHARP-ANGLED CRUSHED STONE OF UNIFORM QUALITY, MEETING THE SPECIFICATIONS OF NYSDOT ITEM 703-02, SIZE DESIGNATION 3-5 OF TABLE 703-4. STONE MAY BE PLACED IN FRONT OF, AND SPREAD WITH A TRACKED VEHICLE. GRAVEL SHALL NOT BE COMPACTED
- GEOGRID SHALL BE MIRAFI BXG110 OR APPROVED EQUAL. GEOGRID SHALL BE DESIGNATED BASED ON EXISTING SOIL CONDITIONS AND PROPOSED HAUL ROAD SLOPES.


TYPICAL ELECTRICAL TRENCH DETAIL

- WOVEN GEOTEXTILE (MIRAFI 500X OR EQUAL) SHALL BE INSTALLED BETWEEN GEOGRID AND
- NATIVE SOIL IN AREAS OF POOR DRAINAGE OR SOILS CONSISTING OF EXCESSIVE FINE MATERIAL IF MORE THAN ONE ROLL WIDTH IS REQUIRED, ROLLS SHOULD OVERLAP A MINIMUM OF 6 INCHES.
- REFER TO MANUFACTURER'S SPECIFICATION FOR PROPER TYING AND CONNECTIONS.
- 7. LIMITED USE PERVIOUS ACCESS ROAD SHALL BE TOP DRESSED AS REQUIRED WITH ONLY 1-4" CRUSHED STONE MEETING NYSDOT ITEM 703-02 SPECIFICATIONS.

BASIS OF DESIGN: TENCATE MIRAFI BXG110 GEOGRIDS; 365 SOUTH HOLLAND DRIVE, PENDERGRASS, GA; (800) 685-9990 OR (706) 693-2226; WWW.MIRAFI.COM








STORM CULVERT END SECTION DETAIL

SCALE: N.T.S.

EVERGREEN TREE PLANTING DETAIL



SCALE: N.T.S.

- REMOVE TOPSOIL AND ALL UNSUITABLE MATERIAL AS REQUIRED AND REPLACE WITH GRAVEL.
- ACCESS DRIVES TO SLOPE IN THE DIRECTION OF THE EXISTING GRADE AT A MINIMUM OF 2.0% DRIVEWAY SHALL BE GRADED TO ALLOW STORMWATER TO SHEET ACROSS IT AND TO PREVENT

GRAVEL ROAD DETAIL

NO TRESPASSING HIGH VOLTAGE TRESPASSERS WILL BE PROSECUTED TO THE FULLEST EXTENT OF THE LAW

HIGHBANKS SOLAR 24-HOUR EMERGENCY LINE (XXX) XXX-XXXX

NOTE: SIGNS TO BE POSTED EVERY 200' ALONG FENCE.

SCALE: N.T.S.

TAIL ANK BANK DE $\mathbf{\Omega}$ HGH SITE H **C6.0**

PROJECT NO: 3576-001


OLAR

S

EERS

LIMITED USE PERVIOUS ACCESS ROAD DETAIL SCALE: N.T.S.

TRESPASSING SIGN DETAIL



DRAWN BY: CHECKED BY: JUNE 19, 2024

RCHIT EERS

 \bigcirc OLAR BANK $\mathbf{\Omega}$ HGH E E

C6.1

PROJECT NO: 3576-001

